

SOUTH KENTUCKY RECC
SOMERSET, KENTUCKY 42501

APPENDIX A OF P.S.C. KENTUCKY NO. 5

A Sub-division of which 113 lots are served Underground.
The line designed at 7.2 KV Primary voltage, using loop feed:

Underground Cost per Foot	\$8.78
Overhead Cost per Foot	2.70
Average Cost Differential	\$6.08

Underground Cost Computation

	<u>Footage</u>	<u>Material</u>	Estimated: <u>Trench, Sand Backfill, Backhoe</u>	<u>Initial Labor & Overhead</u>	<u>Total Cost</u>
Job Totals	33,518	\$95,861.48	\$69,294.93	\$129,044.30	\$294,200.71
Cost Per Foot		2.86	2.07	3.85	8.78

TYPICAL ROCK CLAUSE: An additional \$47.67 per linear trench foot shall be charged where extreme rock conditions are encountered; such conditions being defined as limestone or other hard stratified material in a continuous volume of at least one cubic yard or more which cannot be removed using ordinary excavation equipment.

PUBLIC SERVICE COMMISSION
OF KENTUCKY
EFFECTIVE

MAY 01 1985

PURSUANT TO 807 KAR 5:011,
SECTION 9(1)

BY: *J. Keith Sloan*

DATE OF ISSUE APRIL 26, 1985 DATE EFFECTIVE MAY 1, 1985
Month Day Year Month Day Year

ISSUED BY *J. Keith Sloan* President P.O. Box 910 Somerset, KY
Name of Officer Title Address

C5-86